

Details of Project Scope of Sewerage Projects in Bidding Stage		
Name		Scope
01	JayawardanaPura/ Kotte Wastewater Disposal Project	<p>Project Details</p> <ul style="list-style-type: none"> <li>y Population coverage : 138,300</li> <li>y Sewer network : 137 km</li> <li>y Sewer pumping mains : 15 km,</li> <li>y Sewer lifting stations : 19 Nos,</li> <li>y 1,500 mm dia.Long Sea outfall :1.7 km</li> <li>y Implementation : 60 Months</li> </ul>
02	Hambantota Wastewater Disposal Project	<p>Project Details</p> <ul style="list-style-type: none"> <li>y Population coverage : 30,400</li> <li>y Sewer network : 115 km</li> <li>y Pumping stations : 12 Nos.</li> <li>y HDPE Pumping mains : 16 km</li> <li>y Treatment Plant : 12,000 m3/day</li> <li>y Treated effluent pumped to the abundant irrigation tank</li> <li>y Implementation : 48 Months</li> </ul>
03	Maharagama and Boralesgamuwa Wastewater Disposal System	<p>Project Details</p> <ul style="list-style-type: none"> <li>y Population coverage : 27,300</li> <li>y Sewer reticulation system : 36 km</li> <li>y Sewer pumping main :10.6 km</li> <li>y Sewer pumping stations :12 Nos.</li> <li>y Implementation : 36 Months</li> </ul>

Details of Project Scope of Sewerage Projects in Bidding Stage		
04	Negombo WW Disposal System	<p>Project Details</p> <ul style="list-style-type: none"> <li>y Population coverage : 86,700</li> <li>y Main sewer network : 47 km</li> <li>y Pumping stations : 10 Nos.</li> <li>y HDPE Pumping mains : 6.9 km</li> <li>y 1,000mm dia. Sea outfall : 820 m</li> <li>y Implementation : 36 Months</li> </ul>
05	Chilaw WW Disposal System	<p>Project Details</p> <ul style="list-style-type: none"> <li>y Population coverage : 4,700</li> <li>y Sewer network : 11 km</li> <li>y Pumping stations : 04 Nos.</li> <li>y Pumping mains : 1.9 km</li> <li>y Treatment Plant : 1000 m3/day</li> <li>y 400mm dia. Sea Outfall : 500m</li> <li>y Implementation : 36 Months</li> </ul>
06	Puttalam WW Disposal System	<p>Project Details</p> <ul style="list-style-type: none"> <li>y Population coverage : 7,200</li> <li>y Sewer network : 13 km</li> <li>y Pumping stations : 05 Nos.</li> <li>y Pumping mains : 2.3 km</li> <li>y Treatment Plant : 1,150 m3/day</li> <li>y 400mm dia. Sea Outfall : 500m</li> <li>y Implementation : 36 Months</li> </ul>
07	Kattankudy WW Disposal System	<p>Project Details</p> <ul style="list-style-type: none"> <li>y Population coverage : 79,000</li> <li>y Sewer reticulation system : 44 km</li> <li>y Sewer pumping main : 08 km</li> <li>y Sewer pumping stations : 10 Nos.</li> <li>y Treatment Plant : 10,500 cum/day</li> <li>y 1,200mm dia. Sea Outfall : 700 m.</li> <li>y Implementation : 48 Months</li> </ul>